17 ACCESS AND PARKING

17 Introduction 17-2
17.1 Access, Parking and Servicing 17-2
17.2 Bicycle Parking and End-of-trip facilities 17-7
17.3 Electric Vehicle Charging 17-9
17.4 Car Share Service Parking 17-9
17.5 Parking Contributions 17-10
17.6 Application Requirements 17-10
17.7 Glossary 17-12
17.8 Maps 17-14

17 ACCESS AND PARKING

INTRODUCTION

This Part of the DCP establishes objectives and controls in the Albury LGA for:

- Access, parking and servicing;
- Bicycle parking and end-of-trip facilities;
- Electric vehicle charging;
- Car share service vehicles;
- Parking contributions; and
- Application requirements.

Technical studies and documents have been used to determine prescriptive parking requirements for each land use. These include, but are not limited to, relevant State Environmental Planning Policies (SEPPs), *Guide to Traffic Generating Developments*, (Version 2.2, published by the Roads and Traffic Authority October 2002), and the AlburyCity CBD Parking Strategy 2020-2025. These parking requirements are discretionary and are to be considered in conjunction with existing parking and traffic conditions in the vicinity of the property.

The use of the terms **pedestrian** and **walking** throughout this Part of the DCP includes people who use a mobility scooter, walking frame, and are in a wheelchair, or 'walk' using other mobility devices. A complete glossary of terms used in this Part of the DCP is provided in Section 17.7.

In the event of a discrepancy between the parking rates specified in this Part of the Albury DCP and another Part of the DCP or AlburyCity Engineering Guidelines, this Part of the DCP shall prevail.

17.1 ACCESS, PARKING AND SERVICING

Objectives

1. To provide safe, convenient, and equitable access to parking areas in new developments.

2. To design parking areas that improve pedestrian safety, streetscape amenity and shade.

3. To facilitate an appropriate level of on-site parking provision.

4. To minimise the impact of vehicle movements and traffic congestion on local streets.

5. To minimise the visual impact of on-site parking.

Controls

i. This Part of the DCP applies to development that includes one or more of the following:

a) New floor space or buildings;

b) Change of use.

ii. Development shall provide the minimum on-site parking as set out in and **Table 17.1.1 and Table 17.1.2;** provided according to the requirements set out in the *Guide to Traffic Generating Developments* (Version 2.2, published by the Roads and Traffic Authority October 2002 (or as updated)) or by a relevant *State Environmental Planning Policy* (SEPP), whichever is lesser, and noting the following:

a) **Identified Areas** as per Section 17.8 Maps;

b) When the calculation results in a part or fraction of a number (e.g. 0.3), the minimum number of parking spaces is to be rounded up to the nearest whole number (e.g. 1);

c) Where a combination of uses is intended, the total parking requirements shall be the sum of the requirements for the various uses;

d) Where a variation to the total number of parking spaces meets the objectives of Part 17 and Application Requirements in Section 17.6.

iii. Table 17.1.1 – On-site parking

Land use	Rate
Agritourism	1 per 25m^2 GFA
Artisan food and drink premises	1 per 25m^2 GFA, or nil in **Identified Areas** where the building GFA is less than 500m^2
Business premises or Office premises	1 per 40m^2 GFA
Caravan Park, Camping Ground, Eco-Tourist facility or Farm Stay Accommodation	1 per camp site, moveable dwelling, or cabin plus 3 visitor spaces
Centre-based child care facility	1 per 4 children
Community facility	1 per 30m^2 GFA
Distribution Centre or Warehouse	1 per 100m^2 GFA
Education establishment	Parking study

	Land use	Rate
	Entertainment facility or Function Centre	Parking study
	Food and drink premises	1 per 25m^2 GFA, or nil in **Identified Areas** where the building GFA is less than 500m^2
	Health Consulting Rooms or Medical Centre	1 per 30m^2 GFA
	Hardware and building supplies	1 per 100m^2 GFA. The first 2 spaces must be suitable for cars with a trailer
	Hospital	1 per 2 beds plus 1 per 2 staff (on-duty at the same time) plus 2 ambulance parking spaces
	Industry	1 per 100m^2 GFA
	Light industry	1 per 80m^2 GFA
	Market	1 per stall, or nil in **Identified Areas**
	Pub or Small bar	1 per 25m^2 GFA, or nil in **Identified Areas** where the building GFA is less than 500m^2
	Recreation facility (indoor)	1 per 25m^2 GFA
	Recreation facility (outdoor)	1 per 150m^2 of playing area
	Retail premises	1 per 40m^2, or nil in **Identified Areas** where the building GFA is less than 500m^2
Residential Subgroup	**Residential Subgroup**	
	Dwelling or Dual Occupancy	1 per dwelling
	Multi Dwelling Housing or Residential Flat Building	1 per dwelling, plus visitor Visitor: 1 per 5 dwellings (One visitor space may have a dual use as designated car wash bay)
	Co-living housing, Boarding Houses, or Group homes	0.2 per private room (Accessible Areas) or 0.5 per private room, plus visitor Visitor: 1 per 10 private rooms
	Independent living unit	0.5 per private room
	Hostel	1 per 10 beds plus 1 per 2 staff (on-duty at the same time), plus 1 ambulance parking space
	Residential care facility	1 per 15 beds plus 1 per 2 staff (on-duty at the same time), plus 1 ambulance parking space
	Rural industry	1 per 100m^2 GFA
	Restricted premises or Sex service premises	1 per 40m^2 GFA
	Specialised retail premises	1 per 50m^2 GFA
	Storage premises	1 per 80m^2 GFA
	Tourist and visitor accommodation	1 per private room, or 0.5 per private room in **Identified Areas**

Land use	Rate
Vehicle body shop or Vehicle repair station	1 per 20m^2 GFA
All other land uses	To the satisfaction of Council

Note: Above land use terms are as defined in the *Albury Local Environmental Plan 2010*

iv. Table 17.1.2 – On-site Disability permit parking*

Land use	Rate
Commercial Premises	1 disability permit parking space per 33 car parking spaces
Recreation Facilities	
Multi Dwelling Housing or Residential Flat Building	
Early Education and Care Facilities	The first space must be a disability permit parking space, then 1 disability permit parking space per 33 car parking spaces provided thereafter
Health Services Facilities	

**Accessible space as set out in AS/NZS 2890.6:2009, Parking facilities, Part 6: Off-street parking for people with disabilities*

v. All vehicles (including trucks) must enter and exit the property in a forward direction.

vi. New driveways should be provided from a rear lane or secondary street frontage, wherever practical.

vii. Parking areas are to be consolidated within the property and vehicle access crossings minimised.

viii. All loading and unloading of vehicles must occur within the property boundary.

ix. A schedule for the management of site facilities and services (e.g. arrival of delivery and waste management vehicles), should be prepared to coordinate the use of loading bays on busy or intensive sites or to enable their shared use.

x. Avoid parking layouts that require pedestrians (who have not arrived by car) to move through a car park to access the primary building entry.

xi. The building entry should be visually prominent from the primary street with an appropriately sized awning for weather protection.

xii. The impact of an at-grade, surface parking area is to be minimised by:

a) Limiting the size to a maximum of 100 parking spaces;

b) Locating the parking area on the side or rear of the lot away from the street frontage or behind the building line;

c) Providing shade trees species (minimum mature height of 8m) for amenity and to address urban heat, between parking bays at a rate of 1 tree per 6 parking spaces;

d) Integrating architectural and landscape design elements;

e) Considering Water Sensitive Urban Design and passive irrigation (e.g. kerb cut out's, paving material, tree pit or similar).

xiii. Parking areas with 100 or more parking spaces must:

a) be either incorporated within the building footprint or consolidated into a multi-deck facility;

b) provide 4 motorcycle parking spaces for every 100 car parking spaces;

c) consider floor-to-floor heights that permit conversion to different uses, typically no less than 4 metres on the ground floor and no less than 3 metres on higher floors

d) consider a passenger drop-off and pick-up area close to the building entry;

e) provide appropriate signs for accessible wayfinding.

xiv. Access to the property, parking areas, driveway widths, turning circles, dimensions of loading bays and openings and ramps must be designed in accordance with Australian Standards (AS2890 series) specifically to:

a) Satisfy vehicle dimensions (including service vehicles) and manoeuvring;

b) Satisfy sight line requirements by limiting visual obstruction at driveways for pedestrian safety (i.e. low, stepped wall or chamfered building edges);

c) Ensure the maximum vehicle ramp grade for ramps less than 20 metres is 1:5 (20%) and 1:6 (16.6%) thereafter, and that maximum changes of grade do not exceed 11% (except where transitions comply with AS2890.1);

d) Ensure any pedestrian ramps are at a maximum grade not greater than 1:14;

e) Locate disability permit parking spaces at the ground floor or adjacent to the most convenient building entry; noting that the bay dimensions must not conflict with ceiling height, driveways or vehicle ramps;

f) Include a safe, continuous, and step-free path of travel from the disability permit parking bay to the building entry and connect to the external footpath network.

xv. Where mechanical parking is proposed (e.g. car stackers), a Parking and Access Report may be required to ensure:

a) A maximum of two stacking spaces associated to the same strata title;

b) Queueing, loading and retrieving of vehicles is to be contained within the property boundary;

c) Clear signage with any vehicle type limitations for the parking system.

xvi. Parking areas are to be adequately finished, with sealed surfaces or paving material, internal drainage systems, line markings, appropriate kerbing, paved aisle dividers and/or wheel stops in accordance with *AlburyCity Engineering Guidelines for Subdivisions and Development Standards* and the Austroads *Guide to Traffic Management; Part 11: Parking* (or as updated).

xvii. Outdoor and security lighting to parking areas shall be designed to minimise light pollution in accordance with Australian Standard 4282. If the site is in proximity to a Conservation Zone the lighting design is to reference the *National Light Pollution Guidelines for Wildlife, May 2023 Version 2.0* or as updated.

17.2 BICYCLE PARKING AND END-OF-TRIP FACILITIES

Objective

1. To increase cycling trips through the adequate provision of convenient, safe, and secure amenities.

Controls

i. Provide the minimum on-site bicycle parking as set out in **Table 17.2.1;**

ii. Table 17.2.1 Bicycle parking

Land Use	Rate	Bicycle Parking Security Level *(AS 2890.3**)*
Commercial Premises	1 space per 200m^2 of GFA	B (staff) or
Early Education and Care Facilities		

Land Use	Rate	Bicycle Parking Security Level *(AS 2890.3**)*
Health Services Facilities		C (visitor)
Recreation facilities (indoor)		
Distribution Centre		
Industry	1 space per 10 staff	B (staff)
Warehouse		
Multi Dwelling Housing	2 spaces per dwelling plus 1 visitor space per 10 dwellings	A or B (residents) plus C (visitor)
Residential Flat Building		

**Bicycle parking class is the 'Security Level' as set out in Table 1.1 of AS 2890.3:2015: Parking facilities, Part 3: Bicycle Parking*

iii. Bicycle parking should be:

a) Located at street level or on the ground floor near the primary building entry;

b) Convenient, safe, and secure.

iv. The design of bicycle facilities must generally comply with *AS 2890.3:2015: Parking facilities, Part 3: Bicycle Parking*. In addition, the following design criteria must be met:

a) Ground mounted bicycle rails must be spaced 1 metre apart with sufficient space between the rails for easy access and locking of bicycles;

b) At least 20% of all rails should be floor mounted.

v. Where more than ten bicycle parking spaces are required, standard electrical points should be available for bicycle charging at a ratio of 2 power outlets for every 10 bicycle parking spaces.

vi. Commercial buildings must include end of trip facilities provided close to the bicycle parking area at the following rates:

a) 1 locker for every 2 bicycle parking spaces;

b) 1 shower and change cubicle for 11 to 20 bicycle parking spaces;

c) 1 shower and change cubicle for each additional 20 bicycle parking spaces thereafter;

d) A minimum of 50% of the bicycle parking spaces associated with shower and change cubicle facilities are to be security level B (*AS 2890.3:2015*).

17.3 ELECTRIC VEHICLE CHARGING

Objective

1. To support the provision of EV charging infrastructure in parking areas.

Controls

i. Multi dwelling housing, shop top housing or residential flat buildings are to provide the following suitable electric infrastructure capacity:

   a) Infrastructure and cabling to each car space that can support future installation of Level 2 (Mode 3) 32 Amp EV car charging.

ii. In other parking areas consider provision of wiring conduits and charging point within the parking space to assist future provision for Electric Vehicle (EV).

iii. EV spaces are to be clearly signed and line marked as an “EV” space.

17.4 CAR SHARE SERVICE PARKING

Objective

1. To support car share services and reduce the reliance on private vehicle ownership.

Control

i. Residential developments with over 30 units should consider parking spaces allocated specifically for car share vehicles:

   a) Car share service parking spaces must be highly visible and easily accessible to the public. These spaces must be located on the ground floor, or close to the primary entry into the car park;

b) A nationally recognised[1] Car Share Service provider is to be given access to the car share service parking spaces and contracted to provide car share services at no cost.

17.5 PARKING CONTRIBUTIONS

Objective

1. To accept or require the payment of a parking contribution in lieu of the provision of on-site parking.

Controls

i. If a proposed development does not comply with the rates in **Table 17.1.1**, Council will consider an offer to make a monetary contribution towards parking, provided the offer is made as a Voluntary Planning Agreement in accordance with Section 7.4 (1) of *Environmental Planning and Assessment Act 1979.*

17.6 APPLICATION REQUIREMENTS

i. In relation to access and parking, a development application must show consideration of the following factors:

a) Amount of travel generated by the proposed land use and trading hours (i.e. compliance with parking rates);

b) Impact of parking on traffic generation and potential congestion of surrounding road network;

c) Driveway locations and design that minimise negative impacts on pedestrian or bicycle movements;

d) Safe pedestrian access, vehicle clearance widths, circulation and parking layout;

e) Car parking siting, access location and design including swept path analysis and bay allocation or restrictions;

[1] Nationally recognised in this context refers to an operator that is operating in more than one Australian State or Territory

f) Prioritisation of specific users being people with disability, parent with pram, click and collect and ride share;

g) Provision of adequate bicycle, end-of-trip facilities, motorcycle and accessible parking;

h) Provision of designated loading areas for service vehicles;

i) The *AlburyCity Engineering Guidelines for Subdivisions and Development Standards,* relevant Australian Standards and the Austroads *Guide to Traffic Management; Part 11: Parking.*

ii. A development application seeking a reduction in the minimum parking requirement (refer **Table 17.1.1**), may require a Traffic Impact Assessment Report, and show consideration of the following factors:

a) Demonstrated alignment with a strategic plan or policy document;

b) The adequate provision of pedestrian and bicycle facilities;

c) The amount of related activity[1] and availability of parking in the surrounding area (including public parking areas within 400 metres of the premises);

d) On-street parking capacity (including timed parking areas), proximity to public transport and diversity of nearby land uses;

e) Impact of parking on traffic generation and potential congestion of surrounding road network and road users (including pedestrians, bicycles and vehicles);

f) The likely demand, mix and intensity of surrounding land uses and whether people might prefer to park in a nearby location (including surrounding parking area) with a view to visiting multiple destinations in the area (i.e. linked or multipurpose trips);

g) Any shared parking approaches that utilise nearby public parking areas, particularly where surrounding uses have different parking demand profiles (in terms of the timing of demand peaks during the day, night or throughout the week);

h) Any green and active travel plans to minimise reliance on car access and improve sustainable transport options;

[1] Related Activity in this context is referring to other land uses that could create linked trips. The activities do not need to be similar to the development application. The greater the diversity of nearby activities the more chance there is for linked trips resulting in fewer parking spaces being required for the development application.

i) Ride share or car share services available to reduce total parking demand;

j) Whether the development facilitates the conservation of a heritage item (under Section 5.10 (10) of the *Albury Local Environmental Plan 2010*) or a heritage conservation area.

iii. A development application that seeks to create significant additional parking (beyond the minimum rates specified by this Part of the DCP) or introduce an unacceptable impact on existing road system may require a Traffic Impact Assessment Report prepared by a suitably qualified person. This Traffic Impact Assessment Report should contain the following information:

a) Explanation of the site context;

b) Explanation of the development proposal and how it relates to the site context including opening hours, staff arrangements (number and shift times), expected demand peaks and duration by day of the week, seasonality, and any collaboration with nearby businesses;

c) Explanation of the total travel expected to be generated and the likely breakdown of modes used to access the property at non-peak times and at peak-times (Include any assumptions and discounts to those assumptions if applied);

d) Existing transport network conditions, starting with the quality and extent of pedestrian and bicycle access, access from nearby public parking, service access, access by car (including traffic volumes and existing nearby intersections), the nearest public transport stops and access by large groups (if relevant);

e) Access principles applied to the design including ensuring built form provides premium access for people with disability (particularly those who cannot drive) and prioritising access to the development by sustainable modes;

f) Impact assessment including assumptions, background traffic growth, intersection operational characteristics, existing safety issues and analysis of impacts (in terms of safety and delay) on pedestrians, bicycle riders, public transport and general traffic;

g) Recommended impact mitigation measures, including how to constrain negative impacts of transport and access;


17.7 GLOSSARY

All terms in this Part of the DCP have the same meaning as in the *Albury Local Environmental Plan 2010* (Albury LEP 2010), where provided.

Accessible area	As defined by the *State Environmental Planning Policy Housing 2021* (Housing SEPP 2021)
At-grade, surface parking	means a parking area at the ground level without additional levels above.
Australian Standards	Is taken to be a reference the following documents, where relevant and as updated: • *AS/NZS 2890.1: Parking facilities, Part 1: Off-street car parking;* • *AS 2890.2: Parking facilities, Part 2: Off-street commercial vehicle facilities;* • *AS 2890.3: Parking facilities, Part 3: Bicycle parking;* • *AS/NZS 2890.6: Parking facilities, Part 6: Off-street parking for people with disabilities;* • *AS1428.1: Design for access and mobility–General requirements for access – new building work;* • *AS 4282: Control of the obtrusive effects of outdoor lighting.*
Carshare service	A service provided whereby a driver can rent a vehicle by the hour at a relatively low cost. These services reduce the barrier to entry, and make car use more affordable. They also reduce the cost of transport and the cost of living for users.
End-of-trip Facilities	means designated amenities provided at the end of a journey that support people who cycle, jog or walk and includes secure bicycle parking, locker facilities, toilets, changing rooms and may also include shower cubicles.
EV	Electric Vehicle including plug-in electric hybrid vehicles.
Green Travel Plan	A plan or strategy that identifies issues and opportunities to improve active transport outcomes and public transport services. Typically a Green Travel Plan will include incentives to encourage future residents, staff and visitors to use sustainable modes of transport

	to access the property. They can actively discourage car use in some situations.
Identified Areas	means as per Section 17.8 Maps, **Identified Areas DCP Map**.
Small bar Staff	means a small bar within the meaning of the *Liquor Act 2007*. Any member of a business employed on a short-term or long-term basis.
Vehicle access crossing	means an access point from the road to the property, also known as a driveway.

17.8 MAPS



Albury - Identified Area DCP Map

N

MAP GRID AUSTRALIA, ZONE 55
TRANSVERSE MERCATOR PROJECTION
HORIZONTAL DATUM: GEODETIC DATUM AUSTRALIA 1994
VERTICAL DATUM: AUSTRALIAN HEIGHT DATUM 1972
PRODUCED by the GIS Team, Engineering Group, AlburyCity.


Whilst all care has been taken in the preparation of this cadastral base map, AlburyCity accepts no responsibility for the accuracy of any information shown. Users should rely on their own enquiries in order to validate information shown on this map. AlburyCity - Copyright Reserved.

SCALE:	1:10,000
DRAWN:	Josh.Bruni
DATE:	2/07/2024 3:18 PM

0 180 360 540 720 Meters

AlburyCity

Document Path: G:\2024\GIS\2024 Project \2024 Project\2024 Project.aprx



Lavington - Identified Area DCP Map

N

MAP GRID AUSTRALIA, ZONE 55
TRANSVERSE MERCATOR PROJECTION
HORIZONTAL DATUM: GEODETIC DATUM AUSTRALIA 1994
VERTICAL DATUM: AUSTRALIAN HEIGHT DATUM 1972
PRODUCED by the GIS Team, Engineering Group, AlburyCity.

Whilst all care has been taken in the preparation of this cadastral base map, AlburyCity accepts no responsibility for the accuracy of any information shown. Users should rely on their own enquiries in order to validate information shown on this map. AlburyCity - Copyright Reserved.

SCALE:	1:8,500
DRAWN:	Josh.Bruni
DATE:	2/07/2024 3:08 PM

0 150 300 450 600 Meters

AlburyCity

Document Path: G:\2024\GIS\2024 Project \2024 Project\2024 Project.aprx